

**Attachment 1
Church Street Park
Lighting Upgrade Project**

Crane Matting Rental

Rental Vendor to furnish, deliver, install, relocate, and pickup / remove at the end of the rental period - 430 (each) Mega Deck® HD + composite mats with MDX connection system. Rental period is estimated to be 4 weeks (one month).

Quote to include pricing for Day, Week, and 4-Week periods, delivery and pickup.

Approximate layout of mats as shown in the attached plan.

Matting system shall be [Mega Deck® HD + with MDX connection system](#) (or equal), consisting of the following:

- Composite mats for moving heavy equipment through the jobsite. Each unit is 7.5 feet long, 14 feet wide and 4 inches thick, capable of handling loads up to 600 psi. Include the heavy-duty cam locking system and nesting flange overlaps to ensure a strong, stable access path and work surface.
- Each unit shall provide
- Maximum load capacity 4,500 tons at 600 PSI depending on surface conditions
- 1,095 lbs. each
- Unit dimensions 7.5 ft. by 14 ft. by 4 in.
- Useable (due to flange) 6. Ft. L x 13 ft. W x in. H
- Made from high-density polyethylene that incorporates UV resistance, antistatic properties and high-impact resistance

Matting is anticipated to be required from May 1, 2026 to May 29, 2026

Delivery and setup location is: 5817 Cricket Pitch Way Morrisville, NC 27560

Installation contractors will be advised of the following:

1. Installer to confirm required layout and quantity of mats and identify matting areas to the rental vendor.
2. Installer to confirm the schedule and provide rental vendor a minimum of ten (10) business days—preferably fifteen (15) business days from the date it issues a written authorization to the rental vendor to proceed for mobilization of personnel and equipment to the project site.
3. Installer to ensure there are no obstructions so rental vendor can access to areas where mats are to be installed or removed.